DRAFT TENDER SCHEDULE

BRUHAT BANGALORE MAHANAGARA PALIKE

NAME OF WORK:- Improvements to Roads and Drains at Thanisandra ICICI Bank Surrounding Area Roads in Ward No 06 Thanisandra

DRAFT TENDER SCHEDULE

Item No	Description of Work	Unit	Total Quantity as per Estimation	Rate as per estimate in Rs.	
				In Figures	In Words
1	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods omplete as per specifications and directions of the Engineer in charge. 5km lead= 57+2.0x1.28x5 =69.80	Cum	1015.52	207.60	Rupees Two Hundred Seven and Sixty Paise Only
2	Providing and laying Plain cement concrete of mix1:3:6 with OPC cement @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days Including cost of materials,labour, HOM curing form work, Scaffolding and Centering omplete as per specifications and directions of the Engineer in charge.	Cum	312.90	5421.90	Rupees Five Thousand Four Hundred Twenty One and Ninety Paise Only
3	Providing laying plain/ reinforced cement concrete for side Drains Using M20 nominal mix Concrete with OPC at 300kgs.With 20mm and Down size granite metal coarse aggregate at 0.69cum and fine aggregate at 0.43cum Machne mixed, well compacted for wall and Bottom including centering shuttering,cost of materials,HOM of Machinery,Curing Etc.,Complete Excluding cost of Steel as per morth MORTH specification No. 1500, 1700, 2200. Including Cost of material, Labour, HOM Complete as per specifications and directions of the Engineer in charge.	Cum	347.06	7070.20	Rupees Seven Thousand Seventy and Twenty Paise Only
4	Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery omplete as per specifications and directions of the Engineer in charge.	tonne	21.80	65046.90	Rupees Sixty Five Thousand Forty Six and Ninety Paise Only
5	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,omplete as per specifications and directions of the Engineer in charge.(Data Rate)	Sqm	638.94	2337.00	Rupees Two Thousand Three Hundred Thirty Seven Only
6	Providing and Fixing pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,Complete as per specifications and directions of the Engineer in charge.	Sqm	79.38	5418.00	Rupees Five Thousand Four Hundred Eighteen Only
7	Excavation for roadwork in all types of soil by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 1.00 km and Complete as per specifications and directions of the Engineer in charge.	Cum	495.38	56.26	Rupees Fifty Six and Twenty Six Paise Only

Item No	Description of Work	Unit	Total Quantity as per Estimation	Rate as per estimate in Rs.	
				In Figures	In Words
8	Compaction of original ground by mechanical means including filling in depression occuring during rolling including cost of all labour, HOM Complete as per specifications and directions of the Engineer in charge.	Sqm	1100.84	6.36	Rupees Six and Thirty Six Paise Only
9	Construction of granular sub-base Grading-V as Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/ trap/basalt material, mixing in a mechanical mix plant at OMC, Carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98 % proctor density,Complete as per specifications and directions of the Engineer in charge.	Cum	165.13	1994.92	Rupees One Thousand Nine Hundred Ninety Four and Ninety Two Paise Only
10	Cement concrete pavement.Construction of un-reinforced plain cement concrete for pavement, using a grade concrete M30 over a prepared base with OPC coarse aggregate @ 0.69cum fine aggregate @ 0.46cum,coarse and fine aggregate confirming to IS:383-2016,with superplastisiser @3lts confirming to IS9103-2008.mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). & Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished with floaters in a continuous operation including provision of contraction, expansion, construction and longitudinal joints including groove cutting charges, joint filler, separation membrane of impermiable plastic sheet of 125 micron, sealant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades, textured with texturing machine,and curing including cost of all materials,labour,hire charges of machineries,all lead and lift charges etc., Complete as per specifications and directions of the Engineer in charge.	Cum	165.13	5210.96	Rupees Five Thousand Two Hundred Ten and Ninety Six Paise Only

Executive Engineer

BBMP

ಕಂಡಿಕೆ ( ) ರಲ್ಲಿ ವಿವರಿಸಿರುವಂತೆ ಅಂಶಗಳ ಬಗ್ಗೆ
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು( ) ರವರು
ಪ್ರಮಾಣೀಕರಿಸಿಕೊಟ್ಟಿದ್ದು ಸದರಿಗೆ ಒಳಪಡಿಸಿ ಡಿ.ಟಿ.ಎಸ್
ಬಿಲ್ ಸಲ್ಲಿಸಲಾಗಿದೆ.
ಸದರಿ ಪೂರ್ಣಗೊಂಡ ಕಾಮಗಾರಿಯ ಅಳತೆಯನ್ನು ಪರಿಶೀಲಿಸಿ ಖಾತರಿ
ಪಡಿಸಿಕೊಳ್ಳಲಾಗಿದೆ. —
ತಿದ್ದುಪಡಿಗಳ ಒಟ್ಟು ಸಂಖ್ಯೆ : —
ರದ್ದುಗೊಳಿಸಿರುವ ಒಟ್ಟು ಬಿಲ್ಲುಗಳ ಸಂಖ್ಯೆ : —

ಅಭಿಯಂತರರು (ಗುತ್ತಿಗೆ)